



# Midway Road (CR 712)

## From Glades Cut Off Road of Selvitz Road

### Alternatives Evaluation Matrix

Evaluation Criteria	No-Build Alternative	Alternative 1	Alternative 2
		Canal Avoidance 4-Lane Rural with 7-Foot Buffered Bike Lane	Box Culvert 4-Lane Rural with 7-Foot Buffered Bike Lane
Relocations			
Number of residential relocations	0	0	0
Number of business relocations	0	0	0
Number of parcels impacted	0	16	9
Number of Federal properties impacted	0	1	0
<b>Natural, Environmental &amp; Physical Impacts</b>			
Threatened and endangered species	None	No adverse impacts	No adverse impacts
Archaeological/historical sites	None	1	1
Potential high or medium ranked contamination sites	None	3	3
Wetlands (acres)	None	0.13	0.01
Surface Water Impacts (Acres)	None	1.15	3.53
Floodplains (acre-feet)	None	0	0
Potential Section 4(f) resources	None	1	1
Noise	None	TBD	TBD
Social & neighborhood	None	Low	Low
<b>Estimated Costs (Present Day Costs)</b>			
Design (10% of construction)	No cost	\$2,406,000	\$3,071,000
Road right-of-way	No cost	\$10,721,000	\$6,525,000
Wetland mitigation <sup>(1)</sup>	No cost	\$2,000	\$0
Roadway and bridge construction	No cost	\$24,060,795	\$30,706,041
Reimbursable utility/railroad relocation	No cost	\$680,000	\$500,000
CEI (15% of construction)	No cost	\$3,609,000	\$4,605,906
<b>Total Cost</b>	<b>No cost</b>	<b>\$41,479,000</b>	<b>\$45,408,000</b>

**Notes:**

(1) Based on \$9,999 per mitigation credit acre.